# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41704

## APPROVED SCHEDULE - B

**.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020**

**Name of Work:Filling of Pot holes at HMT Layout, BEL Layout, Defence Layout, NTI Layout, Canara Bank Layout and Surrounding areas in Ward No. 09, (Vidyaranyapura). For the year 2019-20**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of A BALAJI ( ) | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 321.39 | Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work | Cum | 1689.08 | Rupees One Thousand Six Hundred Eighty Nine and Eight Paise Only |
| 2 | 2142.6 | Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 finishing the surface to form a smooth continuous surface, all as per clause 3004.2 etc complete as per specifications and directions of engineer in charge of the work | Sqm | 273.76 | Rupees Two Hundred Seventy Three and Seventy Six Paise Only |

Signature of the Contractor

14/08

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

14/08